

STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	Project Number	10	2

Subtotal Description										
Mainline - 2" Milling Areas	Mainline - Transition Areas	Mainline - 3" HMA Overlay Areas	Mainline - Subcut Areas	Mainline - Reconstruction Areas	Approaches					

Spec - Code	Item Description	Unit										TOTALS
202 - 0021	REMOVE AGGREGATE BASE & SURFACING	TON				1,268.5						1,268.5
202 - 0135	REMOVAL OF BITUMINOUS SURFACING	TON					1,236.2					1,236.2
302 - 0120	AGGREGATE BASE COURSE CL 5	TON			39,989.8	10,071.1	637.2	10,412.5				61,110.6
401 - 0050	TACK COAT	GAL	88.5	145.8	29,772.1	228.0	673.8	976.6				31,884.8
401 - 0060	PRIME COAT	GAL			15,639.9	612.1	1,764.6	4,880.4				22,897.0
401 - 0070	FOG SEAL	GAL	88.5	110.8	14,132.2	108.6	299.5	976.6				15,716.2
411 - 0105	MILLING PAVEMENT SURFACE	SY	1,775.0	1,512.0								3,287.0
430 - 0043	SUPERPAVE FAA 43	TON	197.0	266.9	48,908.7	642.6	2,541.0	3,262.4				55,818.6
430 - 5818	PG 58H-34 ASPHALT CEMENT	TON	11.8	16.0	2,933.6	38.5	152.5	193.7				3,346.1

<p>Cumulative Surfacing Summary</p>  <p>Project Description</p> <p>Project Location</p>	<p>This document is preliminary and not for construction or implementation purposes.</p>
---	--