# **MOUNTAIN-PLAINS CONSORTIUM**

MPC 24-523 | K. Sharma

FORT TOTTEN WALKABILITY ASSESSMENT AND RECOMMENDATION REVIEW





A University Transportation Center sponsored by the U.S. Department of Transportation serving the Mountain-Plains Region. Consortium members:

	Technical F	Report Documentation Page
1. Report No. MPC-566	2. Government Accession No.	3. Recipient's Catalog No.
4. Title and Subtitle		5. Report Date
Fort Totten Walkability Assessn	May 2024	
Tott Totton Walkability Addedsin	6. Performing Organization Code	
7. Author(s)	8. Performing Organization Report No.	
Kshitij Sharma	MPC 24-523	
9. Performing Organization Name and Add	10. Work Unit No. (TRAIS)	
North Dakota State University NDSU Dept 2880 PO Box 6050 Fargo, ND 58108-6050	11. Contract or Grant No.	
12. Sponsoring Agency Name and Address	13. Type of Report and Period Covered	
Mountain-Plains Consortium North Dakota State University PO Box 6050, Fargo, ND 58108		Final Report
		14. Sponsoring Agency Code
15. Supplementary Notes		
Supported by a grant from the US I	OOT, University Transportation Centers Pr	ogram
exercise and to destinations such encourages the safe use of exist varied ranges of mobility. The goal the problems facing the Fort Todocuments the current recommendations.	cable if it is easy and safe for pedestrict has schools, stores, parks, and post sting infrastructure while expanding traical of this assessment is to bring all staten community when it comes to walk ended follow-up steps undertaken by the sconsulting firm(s) and will be useful the and future research needs.	offices. A walkable community insportation options for users with takeholders together to identify ing in the area. The review the Spirit Lake Nation's (SLN)

19. Security Classif. (of this report)

Únclassified

Walkability, vulnerable road user, Native American

17. Key Word

pedestrian safety

20. Security Classif. (of this page)

Unclassified

18. Distribution Statement

Public distribution

21. No. of Pages

26

22. Price

n/a

# Fort Totten Walkability Assessment and Recommendation Review

#### Kshitij Sharma

Advanced Traffic Analysis Center Upper Great Plains Transportation Institute North Dakota State University Fargo, North Dakota

# **Acknowledgements** This research was funded by USDOT University Transportation Centers' Mountain-Plains Consortium.

#### **Disclaimer**

The contents of this report reflect the views of the authors, who are responsible for the facts and the accuracy of the information presented. This document is disseminated under the sponsorship of the Department of Transportation, University Transportation Centers Program, in the interest of information exchange. The United States Government assumes no liability for the contents or use thereof.

NDSU does not discriminate in its programs and activities on the basis of age, color, gender expression/identity, genetic information, marital status, national origin, participation in lawful off-campus activity, physical or mental disability, pregnancy, public assistance status, race, religion, sex, sexual orientation, spousal relationship to current employee, or veteran status, as applicable. Direct inquiries to Vice Provost, Title IX/ADA Coordinator, Old Main 201, (701) 231-7708,ndsu.eoaa@ndsu.edu.

#### **ABSTRACT**

A community is considered walkable if it is easy and safe for pedestrians to walk for recreation and exercise and to destinations such as schools, stores, parks, and post offices. A walkable community encourages the safe use of existing infrastructure while expanding transportation options for users with varied ranges of mobility. The goal of this assessment is to bring all stakeholders together to identify the problems facing the Fort Totten community when it comes to walking in the area. The review documents the current recommended follow-up steps undertaken by the Spirit Lake Nation's (SLN) Transportation Department or its consulting firm(s) and will be useful to inform next steps such as identifying funding opportunities and future research needs.

# **TABLE OF CONTENTS**

1.	Intro	oduction		
2.	Site	Site Selection		
3.	Asse	essment Tool	3	
4.	Site	Visit/Assessment	4	
5.	Obs	ervations	5	
6.	Asse	essment Results	13	
7.	Reco	ommendations	15	
	7.1.	Rebuild	15	
	7.2.	Lighting	15	
	7.3.	Needs Assessment	15	
	7.4.	Maintenance	15	
	7.5.	Pet Ordinance	15	
8.	Reco	ommendation Review	16	
9.	Next	t Steps	19	

# **LIST OF TABLES**

## **LIST OF FIGURES**

Figure 2.1	Assessment route map	2
Figure 5.1	Overhanging trees along ND57	
Figure 5.2	Discontinuity in sidewalk	
Figure 5.3	Missing ramp near Four Winds High School	7
Figure 5.4	Slippery road condition	
Figure 5.5	Damaged bike route sign	8
Figure 5.6	Sign post missing sign	
Figure 5.7	Unleashed pet dog	9
Figure 5.8	Puddle of water on damaged sidewalk	
Figure 5.9	Weathered sidewalk and weeds	10
Figure 5.10	A location missing landing for the pedestrian push button	10
	Another location with missing landing for pedestrian push button	
Figure 5.12	Discontinuous sidewalk	11
	Different top layers used for sidewalk	
Figure 6.1	Walkability ratings totals chart	13
Figure 6.2	Most frequently reported problems chart	13
Figure 6.3	Walkability total ratings categories chart	14

#### 1. INTRODUCTION

A community is considered walkable if it is easy and safe for pedestrians to walk for recreation and exercise and to reach destinations such as schools, stores, parks, and post offices. A walkable community encourages the safe use of existing infrastructure while expanding transportation options for users with varied ranges of mobility. This report documents a walkability assessment of the Spirit Lake Nation (SLN) as completed by Upper Great Plains Transportation Institute (UGPTI). The goal of this assessment is to bring all stakeholders together to identify the problems facing the Fort Totten community when it comes to walking in the area.

## 2. SITE SELECTION

At the request of the SLN, UGPTI's Advanced Traffic Analysis Center (ATAC) assessed an approximately three-mile-long loop of sidewalks and crosswalks in Fort Totten. The loop includes access to the high school, health services center, and several tribal offices. Figure 2.1 shows a map of the loop. Dotted lines indicate locations without a sidewalk/crosswalk.



Figure 2.1 Assessment route map

#### 3. ASSESSMENT TOOL

ATAC staff used the walkability checklist from <a href="www.pedbikeinfo.org">www.pedbikeinfo.org</a> as an assessment tool. A brief training prior to the site visit/assessment included background information regarding the checklist and detailed information regarding the rating scale used in the assessment. The checklist includes the following questions:

- 1. Did you have room to walk?
- 2. Was it easy to cross streets?
- 3. Did drivers behave well?
- 4. Was it easy to follow safety rules?
- 5. Was your walk pleasant?

Each of these questions includes a rating from 1 to 6 categorized as below:

- 1. Awful
- 2. Many Problems
- 3. Some Problems
- 4. Good
- 5. Very Good
- 6. Excellent

The corresponding total ratings add up to a range of 5-30 as classified below:

1. $26-30$ Celebrate! You have a great neighborhood for
---

- 2. 21-25 Celebrate a little. Your neighborhood is pretty good.
- 3. 16-20 Okay, but it needs work.
- 4. 11-15 It needs a lot of work. You deserve better than that.
- 5. 5-10 It's a disaster for walking!

#### 4. SITE VISIT/ASSESSMENT

ATAC staff completed the training, site visit, and assessment on November 26, 2019. The assessment began at the Spirit Lake Tribal Planning office and continued around the three-mile loop. The checklists were completed following the assessment. Participants also provided written comments. The comments covered issues including those identified during the assessment and those observed at other times of the year.

#### 5. OBSERVATIONS

The assessment team observed several people walking on the sidewalk, apparently on their regular lunchtime strolls. Several SLN officials and community members participated in the training as well as the assessment and provided valuable comments. The loop presents a convenient opportunity for users to complete a 5K walk/run.

The team observed an overgrowth of trees and shrubs along the sidewalks. The overgrowth encroached upon the walkable areas of the sidewalk as seen in Figure 5.1. Note that the assessment was completed during the fall. During spring, summer, and early fall, the overhanging branches can be expected to drop further and encroach on the sidewalk even more. This overgrowth is not only a sidewalk-constricting nuisance but a hazard with the potential of injuring sidewalk users, especially during low-light hours of the day.

At several locations, as seen in Figure 5.2, the sidewalk had deteriorated, leading to the substantial loss of the wearing course and allowing the subgrade to surface. In these locations, the sidewalk had the appearance of a gravel path. Such conditions, especially during wet weather, are not conducive to walking or running. The issue is particularly precarious for those using wheelchairs and strollers.



Figure 5.1 Overhanging trees along ND57



Figure 5.2 Discontinuity in sidewalk

At some locations, as seen in Figure 5.3, ramps connecting the sidewalk to the crosswalk were missing. They appear to have never been constructed.



Figure 5.3 Missing ramp near Four Winds High School



Figure 5.4 Slippery sidewalk conditions

At several locations, as seen in Figure 5.4, the sidewalk was icy. At multiple locations, signs were missing, graffiti-covered, or otherwise vandalized as seen in Figures 5.5 and 5.6.



Figure 5.5 Damaged bike route sign



Figure 5.6 Sign post missing sign

The team observed unleashed pet dogs near the apparent owner's house as seen in Figure 5.7. This creates an uninviting walking environment that is further exacerbated by a lack of lighting at night or during low-light hours.



Figure 5.7 Unleashed pet dog



Figure 5.8 Puddle of water on damaged sidewalk

Some places had water puddles on the sidewalk. The area under water in Figure 5.8 appears to have been damaged/cracked. Also, note the missing sign on the post to the right. At other locations, most of the walking surface had weathered and weeds were growing where the sidewalk used to be, as shown in Figure 5.9.



Figure 5.9 Weathered sidewalk and weeds



Figure 5.10 A location missing landing for the pedestrian push button

At some locations, landings next to the pedestrian push buttons were missing, as seen in Figures 5.10 and 5.11. At such locations, it can be very difficult to reach the push button, especially for children and other vulnerable members of the community. The landings appear to have never been built.



Figure 5.11 Another location with missing landing for pedestrian push button



Figure 5.12 Discontinuous sidewalk

At several locations, as seen in Figure 5.12, the team found the sidewalk to be discontinuous, especially across driveways. Another discontinuity location was where the sidewalk led into a parking lot; the difference between the parking lot and the sidewalk was not discernible.



Figure 5.13 Different top layers used for sidewalk

In some locations, different top layers (asphalt and concrete) were observed on the sidewalk. A mix of materials, as seen in Figure 5.13, may present challenges for repair and maintenance.

#### 6. ASSESSMENT RESULTS

On average, participants rated their walk and the infrastructure at about 15 as seen in Figures 6.1, 6.2, and 6.3 below. The assessment results also show that most participants agreed that the infrastructure needed a lot of work.



Figure 6.1 Walkability ratings totals chart




Figure 6.2 Most frequently reported problems chart




Figure 6.3 Walkability total ratings categories chart

#### 7. RECOMMENDATIONS

Based on the observations, assessment results, and participant comments, ATAC has the following recommendations.

#### 7.1 Rebuild

Sections of the sidewalks in poor condition should be rebuilt to current standards. In doing so, there should be no discontinuities across driveways or along parking lots. It would likely be beneficial to complete several smaller related work items at the same time, including:

- Installation of missing ramps
- Pavement marking updates
- Missing sign installation
- Damaged sign replacement

#### 7.2 Lighting

Lighting along the sidewalks should be reviewed, especially at locations where the sidewalk is offset by a large distance from the roadway. Additional lighting is necessary to make the sidewalk safe for users.

#### 7.3 Needs Assessment

A needs assessment should be completed to determine if a traffic signal is warranted along any of the locations. The needs assessment should include items such as potential alternatives and countermeasures to ensure that all field equipment and installations are up to current standards and guidelines.

#### 7.4 Maintenance

A review of maintenance practices should be completed. In addition to using plows, brushing snow away from the walking surface should be considered. De-icing and traction improvement strategies should be instituted to maintain sidewalks and shared-use paths in safe walking conditions. Other considerations include regular maintenance of nearby trees/shrubbery and weed control. Trash receptacles could be installed at regular intervals along the entire path to encourage users to keep the area clear of any garbage.

#### 7.5 Pet Ordinance

A local ordinance should be considered to assure that pets, which many assessment participants considered potentially harmful (e.g., unleashed pets), are kept away from the walking area at all times unless leashed.

#### 8. RECOMMENDATION REVIEW

In 2024, the SLN and Upper Great Plains Transportation Institute initiated a review of the recommendations made in the Fort Totten Walkability Assessment completed by the Advanced Traffic Analysis Center in April 2020. The intent of this review is to document the current status of any recommended follow-up steps undertaken by the SLN's Transportation Department or their consulting firm(s). This review will be used to inform next steps such as identifying funding opportunities and future research needs. Table 8.1 provides review of ATAC's recommendations per potential issue as identified during the prior study. In addition to the current status of the recommendation and its corresponding implication(s), this review also includes comments by agency/consulting staff.

Table 8.1 Recommendation review for Fort Totten Walkability Assessment

Issue(a) Decommendation Status Agency/Consulting				
Issue(s)	Recommendation	Status	Agency/Consulting Staff Comments <sup>1</sup>	Implication(s)
=	[ =	[	F	
Discontinuous or	Rebuild	In Progress	Currently, SLN and	Proactive actions by
otherwise			KLJ have been	Spirit Lake Nation in
weathered			working on a	trying to better
sidewalk, missing			construction project	understand and
ramps, inadequate			plan, which could be	research the existing
water drainage,			ready for a bid opening	conditions, with help
missing landings			in March of 2023. The	from KLJ consultant
for pedestrian push			project consists of	and UGPTI
buttons,			sidewalk construction	researchers, have
			and improvements on	helped identify
			the north side of ND	solutions. Once the
			#57 and will serve a	reconstruction
			school for children	projects are
			living in that area. The	completed, the
			current estimated cost	citizens and visitors
			of the project is	may enjoy the use of
			\$700,000. This	adequately designed
			estimate will be	and well-maintained
			revised with more	pedestrian facilities
			current prices and will	not only within Fort
			likely increase by 20%	Totten but all the way
			to 30%. The project is	to Devils Lake.
			a direct result of the	00 2 0 1110 201101
			study they had on file,	
			and funding from the	
			NDDOT was also	
			recommended by the	
			RTSSC team, which	
			may have helped with	
			approvals of the HSIP	
			dollars or other grants.	
			Also, SLN stated they	
			support an NDDOT	
			plan to provide a	
			pedestrian walkway	
			from Fort Totten to	
			Devils Lake. They	
			have also submitted a	

<sup>&</sup>lt;sup>1</sup> Corresponding staff: Clarence Greene, Paul Bjornson

\_

Issue(s)	Recommendation	Status	Agency/Consulting Staff Comments <sup>1</sup>	Implication(s)
			grant application to NDDOT for a grade widening project in the Tokyo, ND, area for safety reasons. Hopes are to build it in 2025.	
Inadequate lighting	Lighting	Not Started	Likely to be partially undertaken in 2025. No current plans to light the walkway.  NDDOT has ND Highway 57 identified as a safety corridor and plans to upgrade the pedestrian lighting to RRFBs.  The project will upgrade the crossings to ADA compliance, with landings in reach of the current pushbuttons.  The plan is to enhance the pavement markings as well.	The (yet to be built/rebuilt) pedestrian facilities, if left unlit during low ambient lighting hours of the day, present an unwelcoming environment, which may at least discourage the use of said facilities; on the other hand, they may also pose as unsafe surroundings. More opportunities for funding in this regard must be pursued, especially in cooperation with NDDOT.  The planned safety corridor, based on available resources, must be studied before and after for aspects such as traffic and pedestrian safety.
Unknown status of needs for traffic control	Needs Assessment	Not Started	Possibility of NDDOT doing counts during safety corridor project to be used for warrant analysis.	Potentially unknown needs within a transportation network may lead to deteriorated traffic operations leading to reduced traffic safety. Impatient drivers may cause traffic safety concerns and crashes potentially involving pedestrians. Higher levels of coordination between agencies with jurisdiction in the area may help formulate a plan for the assessment's required data

Issue(s)	Recommendation	Status	Agency/Consulting Staff Comments <sup>1</sup>	Implication(s)
				collection. Existing infrastructure such as cameras may be utilized to facilitate the data collection.
Overhanging trees, slippery conditions, and damaged/missing signs.	Maintenance	In Progress	Snow removal is currently being done with a skid steer loader and a power broom on the sidewalks. This unit is owned by the fire department.  Planned project will address tree trimming and replace signs.	Continued coordination between the transportation and fire departments is of utmost importance in this case so that the users may continue to enjoy safe walking conditions.
Unleashed pet dog(s)	Pet Ordinance	Completed & Ongoing	A leash ordinance is in effect for stray dog control and no big mean dogs are allowed since a fatality of a person not long ago. Dogs were actively rounded up and brought to an animal shelter this past summer.	With the said actions, the danger posed by unleased and potentially dangerous pet dogs is minimized. This needs to be continued into the future.

#### 9. NEXT STEPS

The following next steps are identified:

- 1. Continue coordination between agencies with jurisdictions within the region.
- 2. Continue getting assistance from consultants as and when needed.
- 3. Continue researching with assistance from university transportation center(s).
- 4. Continue coordination with Fire Department on shared resources.
  - a. Look into getting Transportation Department owned equipment if the need arises.
- 5. Keep the unleashed pet ordinance in place.
- 6. Take steps to address overhanging trees and damaged/missing signs, especially those not currently planned to be replaced on a regular basis in case of vandalism incidents.
- 7. Collect traffic counts, especially at locations where needs are currently unknown.
  - a. Look into using existing infrastructure for traffic data collection if possible.